



HOLLYWOOD BOULEVARD COMPLETE STREETS PROJECT IN HOLLYWOOD

Project Overview

The Florida Department of Transportation (FDOT) has awarded a \$7,667,258.35 contract to Acosta Tractor Inc. for improvements along Hollywood Boulevard from east of City Hall Circle to Dixie Highway. Construction will begin July 10, 2017 and will be completed in Summer 2019.

This project is part of a larger \$160 million investment from the Broward Metropolitan Planning Organization (MPO) to create a safer and healthier communities by providing and enhancing bicycle, pedestrian, and public transportation access throughout the county. For more information about the Broward MPO please visit: www.browardmpo.org.

Project Improvements

- Removing old asphalt and resurfacing the roadway
- Adding decorative lighting
- Widening sidewalks and adding decorative pattern
- Upgrading existing pedestrian signals to countdown timers
- Constructing new median with parallel parking
- Upgrading signs and pavement markings to reflect the new roadway configuration as follows:
 - ◊ Two lanes in each direction throughout the entire corridor
 - ◊ A four-foot bike lane in each direction separated by a two-foot buffer throughout the entire corridor
- Replacing the existing water main and connections at various cross streets

Traffic Impact

- One lane in each direction of Hollywood Boulevard will be maintained throughout construction.
- Traffic will be shifted to either side of the road as needed.
- Traffic in each direction of N/S 24 and N/S 22 Avenue will be detoured around Hollywood Boulevard while crews work at those intersections.
- Lane closure information will be provided in the weekly traffic report distributed by FDOT. For more information, contact Rebecca Guerrero using the information provided below.

Updated August 08, 2017

For Additional Project Information and Updates
Contact Mrs. Rebecca Guerrero, Community Outreach Specialist
Phone: (954) 218-2304 | Email: rguerrero@corradino.com
www.fdot.gov
Innovative, Efficient, Exceptional