



95 EXPRESS

95 Express Phase 3A-2

FPN #: 433108-5-52-01

Contact Us...

Construction Community Outreach Office:

Andrea Pacini
apacini@corradino.com
(954) 299-6561

Or contact:

Christian Rojas, P.E. FDOT
Construction Project Manager
Christian.rojas@dot.state.fl.us
(954) 958-7669

For information about
95 Express including
lane closure
information, please visit:

www.d4fdot.com



95 Express Phase 3A-2 will extend the existing express lanes north from just north of Commercial Boulevard to just south of SW 10th Street in Broward County. One lane will be added and the High Occupancy Vehicle (HOV) lane will be converted to create two express lanes in each direction. This includes ramp signalization from Cypress Creek Road to Sample Road. Other work includes: installing Intelligent Transportation System (ITS) and tolling equipment, widening bridges and installing noise barrier walls at locations along I-95 Northbound between Atlantic Boulevard and Sample Road, and along I-95 Southbound north of Sample Road. Contract time for this \$154 million project began **Friday, January 8, 2016**, with design and construction activities currently underway. Construction began August 21, 2016, and is expected to be completed Spring 2020. **Please note that this schedule is subject to change due to weather or other unforeseen conditions.**

As of **Winter 2018-19**, project activities are as follows:

- Maintenance activities
- I-95 northbound and southbound widening, milling & resurfacing
- Bridge widening at Cypress Creek and FEC railroad tracks
- Opaque Median wall (glare screen) construction
- Swale construction and drainage structure installation
- Installation of Intelligent Transportation System (ITS) Infrastructure along I-95 northbound
- Installation of Ramp Metering Infrastructure at Cypress Creek Entrance ramps
- Installation of new overhead sign structures
- Construction of new pedestrian bridge north of Sample Road ongoing

Lane Closures & Traffic Impacts:

Lane closures occur in the work zone from 10:30 p.m. to 5:30 a.m. Sunday through Thursday. Entrance and exit ramps will be closed as needed.

Upcoming Project Milestones (weather permitting):

- **January/February 2019:** New pedestrian bridge construction north of Sample Road anticipated to be completed
- **January/February 2019:** All bridge widenings anticipated to be completed
- **January/February 2019:** I-95 widening anticipated to be completed
- **January/February 2019:** Placement of Friction Course (final layer of asphalt) will begin project-wide

Maintenance of Traffic:

While the department makes every effort to minimize impacts to motorists, it will be necessary to close travel lanes and detour traffic at various times and locations to complete project-related work safely. **Lane closures will be scheduled to occur during the following days/times:**

I-95 lane closures:

Single lanes Closures:

10:30 p.m. – 5:30 a.m., Sunday through Thursday

Two lanes closed:

11:30 p.m. – 5 a.m., Monday through Thursday

Three lanes closed:

12:30 a.m. – 5 a.m., Monday through Thursday

Four or more lanes closed/full closure:

1 a.m. – 5 a.m.

NOTE: Full closures of I-95 will be required to install overhead signs, etc. These will be advertised well in advance.

Local street lane closures:

Travel lanes on local streets are closed approaching I-95 as needed for project related work. Affected roadways include: Cypress Creek Road, McNab Road, Atlantic Boulevard, MLK/Hammondville Road, SW 15th Street, Copans Road, and Sample Road.

Local street lane closures will occur as needed from 10 p.m. to 5 a.m. Sunday through Thursday. Special coordination will occur as needed for full closures and/or weekend closures. Entrance and exit ramps will be closed as needed with electronic message signs providing advanced notice to motorists.

Project Partners:

95 Express is being developed in partnership with:

- FDOT District Four, FDOT District Six and Florida's Turnpike Enterprises (FTE)
- Broward Metropolitan Planning Organization
- Broward County Transit
- Miami-Dade County Transit
- South Florida Commuter Services

The Design/Build team for this project is Prince Contracting LLC and Parsons Brinckerhoff. HNTB Corporation provides construction engineering and inspection services on behalf of FDOT.

Project Benefits:

The goal of **95 Express** is to keep traffic moving at average speed of 45 to 50 mph in the express lanes. Motorists with a SunPass transponder are able to use these lanes by paying a toll that adjusts or varies by the level of congestion. Tolls will be higher during peak travel times and lower during off-peak travel times. Toll rates will be displayed on electronic message signs so motorists can choose to use the Express Lanes or stay in the non-tolled general use lanes. Tolls are collected electronically by an "open road tolling" (ORT) system – no toll booths and no stopping to pay. Tolls range from 50 cents to \$10.50 in the currently tolled section from SR 112 in Miami-Dade County to the Golden Glades Interchange.

For information about how you can use 95 Express toll-free, please contact South Florida Commuter services by calling 1-800-234-RIDE (7433) or emailing www.1800234ride.com.

